

**Butler Tech**  
**Lesourdsville Project**  
**March 24, 2023**

1. Please note receipt of this addendum.
2. Contractors are responsible to obtain a Permit for the work.
3. The color of the new panels shall match the existing Blue on the main building.
4. The Contractor shall protect the condensing units along the West elevation of the building.
5. Contractor is responsible for contacting Duke Energy to have the electrical lines covered for safety.
6. The existing lightning protection system shall be reinstalled and UL Certified by a qualified Contractor.
7. The new gutters and downspouts shall match the color of the new panels.
8. A shop fabricated panel shall be used to replace the wood siding along the wall on Section B1.
9. The existing box vents shall be eliminated, and a new ridge vent shall be installed.
10. Provide a unit price per s.f. for bad deck replacement.
11. The Owner is to make arrangements for parking so the Contractor can have access for tear-off and staging of the panels.