

[illegible]

Sheet Title
PSEC OVERALL
SITE PLAN

1. ALL DIMENSIONS SHOWN ARE EXISTING AND FOR REFERENCE AND SHALL BE VERIFIED IN FIELD
2. ALL WORK SHALL BE CONSIDERED BASE BID, UNLESS OTHERWISE NOTED
3. SEE SHEET 6000 FOR ADDITIONAL PROJECT GENERAL NOTES AND REQUIREMENTS
4. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND MARKING ANY UNDERGROUND UTILITIES PRIOR TO START OF WORK IN AREAS TO RECEIVE GRADING OR EXCAVATION WORK

- 1 REMOVE PORTION OF EXISTING CONCRETE SIDEWALK SHOWN AS DASHED AND PREPARE ARE TO RECEIVE NEW ASPHALT PAVING
- 2 REMOVE 5'-0" LONG SECTION OF EXISTING SIDEWALK AND PROVIDE NEW CONCRETE SIDEWALK WITH ADJUTING TRUNCATED DOME - SLOPE NEW CONCRETE TO BE FLUSH WITH NEW ASPHALT - SEE DETAIL 5 / CLOT
- 3 NEW CDDT TYPE 6 CURB - SEE DETAIL 3 ON SHEET CLOT
- 4 NEW MEDIUM DUTY ASPHALT PAVING - SEE DETAIL 2 ON SHEET CLOT

SCAF: $1/64'' = 1'-0''$

